

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
			recomm. from GAAC		appropriately.			
260	3	Washrooms upstairs have no grab bars and the toilets have to be higher. Door latches are inadequate.	Add'n'l recomm. from GAAC	2008	Consider installing grab bars, raising toilets and installing power door openers.			
261	1	Wheelchairs for pool users should be available within or near accessible washroom – close to Reception	Add'n'l recomm. from GAAC	2007	Review location of wheelchairs and ensure that they are accessible to people with disabilities who use the pool.			

ACCESSIBILITY BARRIER IDENTIFICATION
GEORGINA SUTTON ARENA

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
9	1	Power operators on doors	Audit, section F, page 67 of Final plan	2007	Consider adding a power operator on doors to accessible washrooms.			
10	1	Lack of power operators	Audit, section d, page 66 of Final plan	2007	Consider adding power operators on interior doors along primary circulation routes to high-use public areas such as the dressing room corridor, and the door from the banquet hall to the upper arena viewing area.			
8 & 11	1	Banquet hall entrance Lack of power operator on the banquet hall doors and the door from the banquet hall to the arena seating area	Audit, section C, page 66 of Final plan Add'n'i recomm from GAAC page 5	2007	Consider adding a power operator to the banquet hall entrance. Install a power operator on the upper banquet hall doors. Install the push button on the wall to the left as you exit the			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
17	1	Glazed doors	Audit Sections C & D, page 66 of Final plan	2008	elevator and have the right hand door open with the power operator. Consider adding decals at eye level on all glazed doors.			
18	1	Some doors incorporate vision panels but are too high	Audit, section F, page 67 of Final plan	2008	Lengthen vision panels where provided so the bottom of the glass is no higher than 900mm. Appropriate vision panels are recommended on all doors.			
26	1	Tripping hazard on abrupt stair nosings	Audit, section E, page 67 of Final plan	2007	Consider adjusting the abrupt nosings that are incorporated into the stairs, such nosing can be a tripping hazard for some users.			
27	1	Front entrance has a curb	Add'n'l recomm. from	2007	Install a colour contrast strip on the nosing at the curb			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
28	1	The stairs in the arena that access the upper viewing area lack colour contrast on the nosings of the stairs	GAAC page 5 Add'n'l recomm. from GAAC page 5	2007	at the front entrance. The riser portion of the stair has a good colour contrast but the nosing requires a colour contrast strip.			
37	1	Signage	Audit, sections D, E & F, page 67 of Final plan	2007	Upgrade directional signage to incorporate high-contrast, tactile pictograms and lettering, mounted at an appropriate reading height.			
38	1	Exit facilities	Audit, section H, page 69 of Final plan	2007	Identify all exit facilities using high-contrast, tactile pictograms and lettering mounted at an appropriate height.			
88	1	Paint on accessible parking very faded	Audit, section A, page 65 of Final plan	2007	Repaint the parking spaces.			
89	1	Not enough accessible spaces and crossing from accessible spaces	Add'n'l recomm from	2007	Two additional accessible spaces be provided directly			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
			GAAC, page 5, Audit, section A, page 65		to the south of the existing spaces, and that the road crossing be not only identified by striping on the pavement, but also have speed bumps on either side of road crossing.			
92	1	Curb ramp at front entrance to overcome the change in level from the roadway to the entrance area	Audit, section B, page 65 of Final plan	2007	Add handrails to the ramp.			
93	1	A person using a long white cane cannot detect the drinking fountain, servery shelf and mailbox in the main corridor area	Audit, section D, page 66 of Final plan	Research 2004	Consider relocating the objects or provide a detectable warning surface on the floor below the objects.			
94	2	Upper viewing area in the arena is not accessible to persons with mobility impairment, due to stairs	Audit, section D, page 66 of Final plan	2008	There is an opportunity to make this area accessible from the banquet hall by replacing two steps with a ramp. Banquet hall is mostly always closed. Signage			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
					needed and attendant support for making area accessible. Use of key or buzzer/ringer to call attendant to open door from the banquet hall to viewing area. In the middle section of the upper viewing area inside the arena, install a raised platform (1830mm wide) with ramps, railings and plexi-glass, to provide additional viewing area for persons in wheelchairs.			
95	1	Upper viewing area in the arena incorporates angled columns that are not detectable to persons with low visibility or using a long white cane	Audit, section D, page 66 of Final plan	2007	Consider adjusting the columns or provide a detectable warning surface on the floor below the columns.			
96	1	The main foyer raised seating area has a ramp but the landing is too	Audit, section D, page 66 of	2007	Adjustments are recommended. Square off the top			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
		small at the bottom and there are only handrails on one side	Final plan Add'n'l recomment from GAAC, page 5		of the accessible viewing area to allow more room for wheelchairs and flare out the ramp to provide easier access and proper landing room. Add colour contrast striping on the base of the ramp and on the front face of the handrail.			
100	1	Doors to the arena area and to the banquet hall feature a thumb latch device that is difficult to operate; many doors feature knob-type hardware	Audit, sections D & F, pages 66 & 67 of Final plan	2007	Replace thumb latches or knob type hardware with door opening devices of a design that does not require tight grasping and twisting of the wrist.			
102	2	Some doors into functional spaces incorporate self-closing devices but do not feature the necessary clear floor space adjacent to the latch side of the door	Audit, section F, page 67 of Final plan	2008	Consider adjustments to provide a minimum clear space of 600mm adjacent to the latch on the pull side of the door and 300mm on the push			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
106	1	Paint scheme does not provide contrasts	Audit, section D, page 66 of Final plan	2007	side. Where it is impractical to provide the necessary space adjacent to the door, consider providing a power operator or hold-open device. Incorporate painting of corridors, specify colours for walls that contrast with the floor colour and door trim. Consider contrast strip.			
111	1	Service counters are too high to be used by persons of short stature (children) as well as wheelchair users	Audit, section G, page 68 of Final plan	2007	Within each service counter provide at least one service space at least 900mm wide, which is no higher than 865mm. Lower counter of the snack bar in the middle to provide persons in wheelchairs and children easier			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
120		Lack of a Unisex washroom	Audit, section H, page 68 of Final plan		access. Consideration should be given to the provision of one unisex washroom.			
121	1	Men's and Women's washrooms in the main foyer are not fully accessible	Add'n'l recomm. from GAAC page 4	2007	Accessible toilet stall should be wider, grab bars need to be relocated, install an adult change table, lavatory and lower hand drier. In men's washroom a colour contrast strip should be installed on partition wall separating urinals.			
131	1	Fire alarm system	Audit, section I, pages 68 & 69 of Final plan	2007	Consider upgrading the fire alarm system to provide visual signalling devices, flashing lights to better accommodate persons who are hard of hearing. Should have sound or beepers at doors to aid in finding			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
132	1	Only one grade-level main entrance exit is available at the main floor level in case of emergency	Audit, section I, page 69 of Final plan	2007	<p>exits for individuals who have visual impairments.</p> <p>The building is sprinklered, it does not require any additional protective measures. Multiple grade-level exits are available from the main floor level. Consideration should be given to upgrading at least one other exit to provide a secondary means of escape that is accessible to persons who are mobility impaired. There are no grade-level exits available from the upper level. However, the banquet hall and the rink may be separated by a</p>			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
					<p>partition that is a fire separation, providing a horizontal exit. Verify that this is the case. If not, consider providing an area of safe refuge, where mobility impaired persons can go in an emergency situation to await evacuation by the fire department. In consultation with the local fire department, it is recommended that emergency evacuation procedures be reviewed, to ensure that appropriate measures are in place to address the needs of persons with disabilities in an emergency</p>			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
133	1	The upper emergency exits from the banquet hall should be upgraded	Add'n'l recomm. from GAAC, page 6	2007	<p>situation. The upper level exits from the banquet hall be raised to provide a level exit and to widen the platform to provide more area for a wheelchair.</p> <p>Exits should be raised to be level with the bottom of the door and the upper landing should be widened to provide an area of safe refuge for persons in wheelchairs.</p>			
136	1	Unobstructed path of travel	Audit, section G, page 68 of Final plan	2007	Access within each individual functional space was not assessed. Ideally, each space should provide an unobstructed path of travel throughout that is at least 920mm wide; also (ideally) it should			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
					contain a 1500mm diameter clear space to allow wheelchair users to turn around.			
235	1	Lack of telephone or telecom system in elevator	Audit, section E, page 67 of Final plan	2007	Install a telephone or other means of communication for use in an emergency within the elevator.			
236	1	A telephone in the lobby does not incorporate TDD	Audit, section J, page 69 of Final plan	2007	Consider replacing one of the public phones with a model that incorporates a TDD unit.			
237	1	The upper viewing area in the banquet hall is always locked	Addit'l recomb. From GAAC page 5	2007	Proper signage needed and attendant support for making area accessible.			
238	1	Controls and operating mechanisms are mounted too high	Audit, section D, page 66 of Final plan	2007	Lower controls and operating mechanisms to no higher than 1200 mm.			
239	4	There are no accessible facilities within any of the rink change rooms. In	Audit, section G, page 68 of	2009	Consideration should be given to providing			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
		<p>dressing rooms #1 and #2, showers are not accessible</p>	<p>Final plan & add'n'l re-comm. From GAAC pages 5 & 6</p>		<p>accessible washroom, showering and changing facilities in two of the dressing rooms. Widen the shower opening to 1100 mm, provide a shower commode or bench, lower showerheads and raise the concrete floor to eliminate step into shower. Move the toilet stall door to the shower entrance to make washroom and shower fully accessible.</p>			
241	2	<p>The banquet hall has a kitchen/bar/servery that is not accessible</p>	<p>Audit, section G, page 68 of Final plan</p>	2008	<p>Consideration should be given to making part of these facilities accessible to persons with</p>			

Barrier #	Ranking #	Barrier to be addressed	Reference	Budget year	Disposition	Year completed	Actual cost	Description of the work completed
242	2	Additional viewing area	Addn'l recomm. from GAAC, page 4	2008	disabilities. The upper viewing area in the arena has a wide enough corridor that can support a raised viewing area for those in wheelchairs.			
281		Steps outside Sutton Arena		2007	Exterior step in front of Sutton Arena door -- colour contrast on nosing.			